

## PROTECT & ACTIVATE YOUR PRODUCT WARRANTY

**It is critical that you have read the Installation & Care documents prior to laying your 'Flexo' rubber product.**

The following key points are extracts from the full instructions. Whilst important, they should be noted in conjunction with the complete document. The Installation Instructions and Care & Maintenance documents are available either online at [www.signaturefloors.com.au](http://www.signaturefloors.com.au) or by contacting Signature Floors Customer Service on **1800 150 554**.

### PRIOR TO INSTALLING

- Check product colours and dye lots.
- Check adhesive instructions.

### WE RECOMMEND

- Signature 2 Part PU Rubber Flooring Adhesive & Signature Acrylic Rubber Flooring Adhesive.
- The Signature 2 Part PU Rubber Flooring Adhesive must be used in areas subjected to heavy traffic or in areas that is subject to direct sunlight.
- Note well all adhesive curing & setting times.

### KEY POINTS TO NOTE

- The product should be unpacked from cartons, stacked face to face, and acclimatized for a minimum of **48 hours**. The site temperature should be stable during that time at between **15° and 29°C**.
- Humidity should not be higher than 70%.
- Block out windows to remove direct sunlight for **48 hours prior to AND after installation**.
- Slab moisture content must be **5.5%** or less, and a minimum temperature of not less than **10°C**.
- Remove any excess adhesive from tile surfaces, before it sets.
- The installation must be rolled with a 40-50 kg roller after installation.
- There should be no foot traffic for **24 hours** and no rolling traffic for **72 hours** after installation.
- It is critical that the Initial Cleaning process is followed precisely as detailed in the Installation Instructions & also in the Care and Maintenance documents. The Initial Cleaning should not be undertaken for at least **24 hours** after installation.

Rubber Checklist  
Document Number: 100015  
Revision No: 01  
Date modified: 29/05/2012

**WARRANTY ACTIVATION**

As the product installer, I have read and understand these key points relating to the installation of Signature 'FLEXO' rubber flooring. I have also noted additional detail in the Installation Instructions. I understand the process for the Initial Cleaning of the product.

Signed..... Dated.....  
(Returning this document will allow us to register this installation for warranty)