

**SCORE**



**SCORE CODA 25**

**au 1800 150 554**  
**nz 0800 150 555**  
**[signaturefloors.com.au](http://signaturefloors.com.au)**  
**[signaturefloors.co.nz](http://signaturefloors.co.nz)**

*Signature*



SCORE



OPUS  
32



REQUIEM  
33



CRESCENDO  
86



BALLAD  
17



MINUET  
15




ETUDE  
11



CANTATA  
34



CHORALE  
62



HYMN  
18




BERCEUSE  
66




OVERTURE  
44




ARIOSO  
98




SCENA  
21




CODA  
25



ORATORIO  
23




MADRIGAL  
29



ELEGY  
71



CAPRICCIO  
99



STROPHIC  
72



STRETTA  
79



SCORE



SCORE STROPHIC 72

SPECIFICATIONS

<b>Product</b>	Score
<b>Product Category</b>	Woven Carpet
<b>Construction</b>	Axminster
<b>Yarn/Fibre</b>	40% NZ Wool, 40% British Wool, 20% Nylon
<b>Pile Weight</b>	41oz
<b>Pile Height</b>	8mm
<b>Pitch/Beat Up</b>	7x8
<b>Backing</b>	Polypropylene
<b>Total Thickness</b>	10.70mm
<b>Carpet Width</b>	366cm

CUSTOM OPTIONS

<b>Pile Weight 46oz (7x9)</b>	MOQ 200m <sup>2</sup>
<b>Pile Weight 51oz (7x10)</b>	MOQ 200m <sup>2</sup>
<b>Colour</b>	MOQ 200m <sup>2</sup>

PERFORMANCE

<b>Traffic</b>	Commercial Heavy Duty
<b>Warranty</b>	Residential 7 Year Commercial 5 Year
<b>Fire Rating ISO 9239.1</b>	>4.5kw/m <sup>2</sup> Critical Radiant Flux
<b>Electrostatic Propensity</b>	<2.2kv

INSTALLATION METHODS

	Dual Bond
	Conventional Lay
	Comfilay underlay recommended

SUSTAINABILITY

Green Label Plus

TECHNICAL DOCUMENTS

- [Installation Guide](#)
- [Maintenance Guide](#)
- [Recommended Adhesives](#)

All edges to be cut & seam sealed prior to installation.

Cut pile carpets, particularly 'plush pile' will in some circumstances exhibit the condition known as 'shading, watermarking or pile reversal'. A cut pile carpet that has 'shaded' will show areas lighter or darker than the surrounding carpet pile. The variation is caused by the reflection of light from pile tufts which come to lay in different directions. It does not affect the wear or durability of the carpet and since it is beyond the control of the manufacturer, it is not recognised as a manufacturing flaw or fault.